

INDIANA DEPARTMENT OF TRANSPORTATION
100 North Senate Avenue Room N758-Cont
Indianapolis, Indiana 46204-2218

Letting of January 13, 2021

January 7, 2021

NOTICE OF REVISION NO. 2
TO CONTRACT NO. R -39293-A

The Schedule of Pay Items was revised as follows: Section 1: line number 0091 quantity was revised. Line numbers 0193 and 0194 were added. A revised Schedule of Pay Items pages 8 and 16 are included herewith.

The Special Provisions page 163 has been revised and a copy is included herewith.

Please substitute the attached sheets for the like numbered sheets that now appear in your copy of the bidding document.

Should you desire to submit a bid, please do so with the basis of the information set out above.

For electronic bids, the prequalified bidders for the above contract shall acknowledge this revision by entering the date of this letter in the appropriate field on the electronic proposal form.

It is the bidder's responsibility to check the Bid Express website for all amendment files prior to the deadline for bid submittal. This includes amendment files that may be generated as a result of administrative changes to the bidding form, which may not be communicated in a revision letter.



Behrooz Vakily
Bid Review Manager

BV/mr/dns

Notice: Notification that a revision was released shall only be sent by email to those subscribing to the INDOT listserver at this address: <http://www.in.gov/dot/div/contracts/letting/Email-Form.html>. The email message includes a link to the extranet site where the revision may be viewed, downloaded and printed. The link is: <http://erms.indot.in.gov/viewdocs/>

For help retrieving electronic documents, please contact Customer Service at 317-234-4949.

**Indiana Department of Transportation**

Letting Date: January 13, 2021

Revision 2: January 06, 2021

Proposal Schedule of Items

Page 8 of 17

Proposal ID: R -39293-A**Project(s):** 1593231, 1700939**SECTION:** 1

PAVEMENT REPLACEMENT AND BRIDGE DECK OVERLAY

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0090	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000 EACH	_____.	_____.
0091	621-06554 SEED MIXTURE U	1.710 LBS	_____.	_____.
0092	621-06574 SODDING	10,392.000 SYS	_____.	_____.
0093	628-09403 FIELD OFFICE, C	30.000 MOS	_____.	_____.
0094	702-51015 CONCRETE, B, FOOTINGS	22.000 CYS	_____.	_____.
0095	703-06028 REINFORCING BARS	612.000 LBS	_____.	_____.
0096	709-51821 SURFACE SEAL	LUMP SUM	LUMP SUM	_____.
0097	714-11191 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 4 FT.	176.000 LFT	_____.	_____.
0098	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	22.000 LFT	_____.	_____.
0099	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	10,122.000 LFT	_____.	_____.
0100	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	3,454.000 LFT	_____.	_____.
0101	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	296.000 LFT	_____.	_____.
0102	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	312.000 LFT	_____.	_____.

**Indiana Department of Transportation**

Letting Date: January 13, 2021

Revision 2: January 06, 2021

Proposal Schedule of Items

Page 16 of 17

Proposal ID: R -39293-A**Project(s):** 1593231, 1700939**SECTION: 1** PAVEMENT REPLACEMENT AND BRIDGE DECK OVERLAY**Alt Set ID:****Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0187	808-75297 TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	335.000 LFT	_____.	_____.
0188	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.000 EACH	_____.	_____.
0189	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	141.000 EACH	_____.	_____.
0190	808-97664 PAVEMENT MESSAGE MARKING, THERMOPLASTIC ADA ACCESSIBLE SYMBOL	2.000 EACH	_____.	_____.
0193	621-04258 SEED MIXTURE , SOIL STABILIZATION	0.610 LBS	_____.	_____.
0194	605-06120 CURB, CONCRETE	343.000 LFT	_____.	_____.
Section: 1			Total:	_____.

SECTION: 2 PAVEMENT REPLACEMENT AND BRIDGE DECK OVERLAY**Alt Set ID:** OP**Alt Mbr ID:** 1

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0191	722-51842 BRIDGE DECK OVERLAY, LATEX MODIFIED	1,032.000 SYS	_____.	_____.
Section: 2			Total:	_____.

GREENFIELD DISTRICT

Contract No. R -39293

		Oz/Acre
Cover Crop		Central
Avena sativa (Seed Oats)		800
Lolium multiflorum (Annual Ryegrass)		
Grasses and Sedges		Central
Andropogon gerardii (Big Bluestem)		32
Bouteloua curtipendula (Side-Oats Grama)		16
Carex bicknellii (Prairie Oval Sedge)		--
Carex granularis (Meadow Sedge)		2
Elymus canadensis (Canada Wild Rye)		48
Elymus virginicus (Virginia Wild Rye)		32
Panicum virgatum (Switchgrass)		14
Schizachyrium scoparium (Little Bluestem)		32
Sorghastrum nutans (Indian Grass)		32
	Total	208.0
	Grand Total (oz/Acre)	1008.0
	Grand Total (lbs/Acre)	63.0

All costs associated with placing the Standard Seed Mixture, U shall be included in the cost of Seed Mixture, U. The Soil Stabilization Mix shall be included in the cost of Seed Mixture.

REPAIR STORM STRUCTURES

Where pipe is removed and an opening remains in an existing storm sewer structure, the Contractor shall plug or otherwise repair the opening. The cost to repair the opening shall be included in the cost of Pipe, Remove. No direct payment will be made to repair an opening in a storm structure.

CAP EXISTING DRAINAGE STRUCTURES

Description

This work shall consist of capping existing drainage structures that are to be abandoned in place.

Materials

Materials shall be 0.75-inch-thick steel plate and earthen backfill.

Construction Requirements

Structures designated to be capped shall be clear of all debris prior to the commencement of the work. Capping of existing structures shall occur only after the structure is no longer used for existing drainage.

Existing structures which are to be abandoned but shall remain in place at the completion of construction shall have a 0.75-inch thick steel plate placed on the top of structure and backfilled with earth.